

RESOLUTION 2020-30

RESOLUTION AUTHORIZING THE AWARD OF A CONTRACT  
WITH AN ESTIMATED COST BETWEEN \$6,000.00 AND \$40,000.00  
WITHOUT PUBLIC ADVERTISING FOR BIDS

WHEREAS, the "Local Public Contracts Law" provides that except for contracts which require the performance of professional services, all contracts or agreements which do not require public advertising for bids and the estimated cost or price is between \$6,000.00 and \$40,000.00, two (2) or more competitive quotations as to cost or price, whenever practicable, shall be solicited by the contracting agent, and the contract or agreement shall be made with and awarded to the lowest responsible bidder; and

WHEREAS, The Bordentown Sewerage Authority has solicited from the following bidders the respective quotations as to price:

<u>BIDDER</u>	<u>PRICE</u>
Univar Solutions	\$11,392.20
Pyrz Water Supply Co, Inc.	\$13,630.00

for the following goods or services:

**Quantity of two 625 Gallon Sodium Hypochlorite Tanks.**

WHEREAS, a Certificate of Availability of Funds has been provided by the designated certifying finance officer and is attached hereto.

NOW, THEREFORE, BE IT RESOLVED, this 16th day of March, 2020, that contracts, be and the same are hereby awarded to:

**Univar Solutions**, in the amount of \$11,392.20 for the goods or services described above.

THE BORDENTOWN SEWERAGE AUTHORITY

Attest:

  
Joseph R. Malone, III, Secretary

By:

  
James E. Lynch, Jr., Chairman

I have reviewed this Resolution and the Certificate of Availability of Funds and am satisfied that an appropriate Certificate of Availability has been provided.

  
Thomas J. Coleman, III, Esquire  
General Counsel

**CERTIFICATE OF AVAILABILITY OF FUNDS**


I, Elizabeth J. Kwelty, Administrative Manager and Certifying Finance Officer of The Bordentown Sewerage Authority, do hereby certify, pursuant to the rules of the Department of Community Affairs, Division of Local Government Services (N.J.A.C. 5:34-5.1 et seq.), that there are available adequate funds for the following proposed contract:

CONTRACT: Two-625 Gallon Sodium Hypochlorite Tanks  
CONTRACTOR: Univar Solutions  
CONTRACT AMOUNT: \$11,392.20  
BUDGETARY LINE ITEMS: 02-004-7610

I certify that the same funds have not been certified as available for more than one pending contract.

03/16/2020

Date

  
Elizabeth J. Kwelty  
Certifying Finance Officer

**THE BORDENTOWN SEWERAGE AUTHORITY  
QUOTATION RECORD FORM**

**PROJECT:** Sodium Hypochlorite Tanks

**ITEM OR SERVICE:** 2 - 625 Gallon Sodium Hypochlorite Tanks

If not awarded to lowest price, explanation: \_\_\_\_\_

1. Vendor: Univar Solutions Price: 11,392.20

Special Terms: \_\_\_\_\_

Solicited By: ☒ Email ☐ Fax ☐ Phone ☒ In Person ☐ Internet

2. Vendor: Pyrz Water Supply Co. Inc. Price: 13,630.00

Special Terms: \_\_\_\_\_

Solicited By: ☒ Email ☐ Fax ☐ Phone ☐ In Person ☐ Internet

3. Vendor: \_\_\_\_\_ Price: \_\_\_\_\_

Special Terms: \_\_\_\_\_

Solicited By: \_\_\_\_\_ Email ☐ Fax ☐ Phone ☐ In Person ☐ Internet

4. Vendor: \_\_\_\_\_ Price: \_\_\_\_\_

Special Terms: \_\_\_\_\_


Solicited By: \_\_\_\_\_ Email ☐ Fax ☐ Phone ☐ In Person ☐ Internet

**AWARDED TO:** Univar Solutions **PRICE:** 11,392.20

**TERMS:** \_\_\_\_\_ **SPECIAL COMMENTS:** \_\_\_\_\_

**PURCHASE ORDER #** \_\_\_\_\_

**SOLICITATION PERFORMED BY:** Charles Blum Jr

  
(SIGNATURE)

**DATE:** 02/19/2020

# Pyrz Water Supply Co. Inc.

P.O. Box 107  
Harleysville, Pennsylvania 19438  
(215) 256-8430 / Fax (215) 256-8567  
www.pyrzwater.com

TO: Bordentown Sewerage Authority

QUOTATION NO: 53735

DATE: Jan 7, 2020

SUBJECT: Sodium Hypochlorite Tank

ATTN: Chuck Bluhm

---

## QUANTITY

## DESCRIPTION

---

We are pleased to quote as follows:

### 625 GALLON DOUBLE WALL TANK

1

Assmann Model IMT0625 Linear Polyethylene Tank

SERVICE: 12.5% Sodium Hypochlorite

- Interior Storage @ ambient temperatures
- Material selection for tank, fittings & gaskets for 12.5% sodium hypochlorite.

CONFIGURATION: Double-wall, vertical, cylindrical, flat bottom, domed top head

CAPACITY: 625 US Gallons (nominal) in straight side

DIMENSIONS: 47 " DIAMETER  
113" OVERALL HEIGHT (not including top accessories)

CONSTRUCTION: Rotationally molded for a seamless, one-piece tank

MATERIAL: Linear Polyethylene (PE)

DESIGN: Tank rated for up to 1.9 specific gravity product  
No internal pressure or vacuum  
No windload or seismic calculations  
Tanks designed and fabricated in accordance with ASTM D1997-98 standards

SUPPORT: Tank to rest flat on floor or pad  
Tank bottom must be fully supported

MANWAY: (1) 16" DIA top access manway with cover

FITTINGS:  
(1) 2" PVC bulkhead fitting with Viton gasket (**FILL**) with 2" fill assembly and antifoam elbow

(1) 1" Titanium double male thru-wall fitting with Viton Gasket  
(**SUCTION**).

(1) 3" PVC Bulkhead fitting with Viton gasket (**VENT**)

(1) 2" PVC Bulkhead fitting, Viton gasket, (**SPARE**)

ACCESSORIES:

NONE

**TOTAL PRICE:** f.o.b. Garrett IN .....\$ 6230.00 X 2

**OPTIONAL ADDERS:**

Reverse Float Level Indicator

If required, please add (\$ 865 each) to above price: \$1730.00

**ESTIMATED FREIGHT:** .....\$1170.00

Not Included: Wiring, piping, installation, sales or use tax or any item not specifically noted above.

We hope to have the opportunity of furnishing the above for you.

Sincerely yours,


PYRZ WATER SUPPLY CO., INC.

Joe Pyrz





ACCESSORIES		
MK	QTY	SIZE DESCRIPTION
A	1	2" PVC BULKHEAD FITTING WITH GASKET
B	1	2" PVC THREADED CLOSE NIPPLE
C	2	2" PVC THREADED TEE
D	2	2" PVC THREADED PIPE PLUG
E	2	2" PVC THREADED PIPE NIPPLE (AS REQUIRED)
F	1	2" PVC SOCKET UNION
H	1	2" CLEAR BUSADA 200 PIPE, THREADED ONE END
K	2	- POLYETHYLENE PIPE SUPPORT BRACKET (SEE RFL_ASM DWG.)
L	2	- ENCAPSULATED DONKER BOLTS
M	1	- POLYETHYLENE INTERIOR FLOAT. (SEE RFL_ASM DWG.)
N	1	- PVC EXTERIOR COUNTER WEIGHT (SEE RFL_ASM DWG.)
P	2	- FABRICATED PVC ROLLER / INSTALLED W/ PE ROD
Q	-	- 1/8" DIA. UHMWPE ROPE

B	CHANGED ROPE MATERIAL FROM POLYPRO TO UHMWPE	6/5/17SR
A	CHANGED TUBING FROM PVC TO BUSADA (EFFECTIVE 5-29-08), DELETED ITEM (G) MALE THRED X COUPLER) AT TOP, DELETED ITEM (J) (FEMALE COUPLER) JOINT CONNECTION	3/24/09 SR
REV	REVISION DESCRIPTION	REV DATE
 <b>Aomann</b> CORPORATION OF AMERICA		300 N TAYLOR ROAD GARRETT, IN 46738 PHONE 6360 337-3161 FAX 6360 337-3728
TITLE REVERSE FLOAT LEVEL INDICATOR FOR VERTICAL STORAGE TANKS		DRAWN BY: <b>S ROWLANDSON</b> DRAWN DATE 3-2-04 DWG NUMBER: <b>RFL-3-31-04</b>
		REV

# ACCESSORIES

MK	QTY	SIZE	DESCRIPTION
A	1	-	POLY-PRO CAP FOR MALE ADAPTER
B	1	-	POLY-PRO MALE THREAD X MALE ADAPTER
C	1	-	POLY-PRO 45° STREET ELBOW
D	1	-	PVC BALL VALVE W/ EPDM SEALS (STANDARD)
E	1	-	POLYETHYLENE PIPE SUPPORT BRACKET, (STANDARD) WITH S/S BOLTS, EPDM ENCAPSULATED HEADS & EPDM GASKET
F	2	-	PVC/ SCH. 80 THREADED 90° ELBOW (STANDARD)
G	1	-	PVC/ SCH. 80 BULKHEAD W/ EPDM (STANDARD)
H	2	-	PVC/ SCH. 80 PIPE (STANDARD)
J	1	-	PVC/ SCH. 80 CLOSE NIPPLE (STANDARD)
K	1	-	X 8" PVC/ SCH. 80 NIPPLE (STANDARD)
L	1	-	FERNCO PIPE CLAMP
M	1	-	PVC/ SCH. 80 45° SLIP ELBOW (STANDARD)

## MATERIALS:

### BULKHEAD FITTING:

PVC CPVC POLYPROPYLENE PVDF (OPTIONAL)

### BALL VALVES:

PVC CPVC POLYPROPYLENE PVDF (OPTIONAL)

### VALVE SEALS:

E.P.D.M. & VITON ONLY

### PIPING, NIPPLES, & ELBOWS:

PVC CPVC POLYPROPYLENE PVDF (OPTIONAL)

### DONKER BOLTS:


SS-EPDM SS-VITON TT-EPDM TT-VITON  
HST-EPDM HST-VITON

### GASKET:

E.P.D.M. VITON XLPE BUNA GORTEX (OPTIONAL)

SIZES AVAILABLE:

1' 2' 3'



A	REV	UPDATED TITLE BLOCK	4/23/09 MG
		REVISION DESCRIPTION	REV DATE
		SALES ORDER	
		300 N TAYLOR ROAD GARRETT, IN 46738 PHONE 650 357-3181 FAX 650 357-3788	
		BRAND JTY D. CRAGER BRAND JTY 5/11/01	
		TITLE FILL LINE ASSEMBLY WITH BULKHEAD FITTING & ANTI-FOAM ELBOW	
		DWG NUMBER	REV
		FL-BH-AF	A





February, 18, 2020 -

Bordentown Sewerage Authority  
954 Farnsworth Ave  
Black Creek WWTP  
Bordentown, NJ 08505  
Chuck Bluhm

Dear Chuck,

Thank you for the opportunity to service your Bordentown NJ plant.

Please find the proposal for 2 – 625 gallon Sodium Hypochlorite 12.5% tanks delivered to Bordentown, NJ. Pricing includes the following:


IMT 625 Tank with bulk heads	\$3,071.60
Bottom outlet valve, load line and RLI	\$1,111.50
1" bulk fitting at bottom of tank 180 degrees	\$ 771.00
Shipping	\$ 742.00
Total	\$ 5,696.10 X 2 tanks = 11,392.20

Univar will have the tanks shipped direct from the manufacturer. Univar will assist with getting the tanks in place. Bordentown will be responsible for hooking up the tanks to their process.

If you have any additional questions please do not hesitate to contact me at 267-784-8382.

Thank you

Christine Richter  
Territory Manager-MiniBulk  
Univar Solutions



ACCESSORIES			DESCRIPTION
NK	QTY	SIZE	
A	1	-	POLY-PRO CAP FOR MALE ADAPTER
B	1	-	POLY-PRO MALE THREAD X MALE ADAPTER
C	1	-	POLY-PRO 45° STREET ELBOW
D	1	-	PVC BALL VALVE W/ EPDM SEALS (STANDARD)
E	1	-	POLYETHYLENE PIPE SUPPORT BRACKET (STANDARD) WITH S/S BOLTS, EPDM ENCAPSULATED HEADS & EPDM GASKET
F	2	-	PVC/ SCH. 80 THREADED 90° ELBOW (STANDARD)
G	1	-	PVC/ SCH. 80 BULKHEAD V/ EPDM (STANDARD)
H	2	-	PVC/ SCH. 80 PIPE (STANDARD)
J	1	-	PVC/ SCH. 80 CLOSE NIPPLE (STANDARD)
K	1	-	X 8" PVC/ SCH. 80 NIPPLE (STANDARD)
L	1	-	FERNCO PIPE CLAMP
M	1	-	PVC/ SCH. 80 45° SLIP ELBOW (STANDARD)

#### MATERIALS:

#### BULKHEAD FITTING:

PVC CPVC POLYPROPYLENE PVDF (OPTIONAL)

#### BALL VALVES:

PVC CPVC POLYPROPYLENE PVDF (OPTIONAL)

#### VALVE SEALS:

EPDM & VITON ONLY

PIPING, NIPPLES, & ELBOWS:

PVC CPVC POLYPROPYLENE PVDF (OPTIONAL)

#### DONKER BOLTS:

SS-EPDM SS-VITON TT-EPDM TT-VITON


HST-EPDM HST-VITON

#### GASKET:

EPDM VITON XLPE BUNA GORTEX (OPTIONAL)

#### SIZES AVAILABLE:

1" 2" 3"

REV	DESCRIPTION	DATE
A	UPDATED TITLE BLOCK	4/23/09 MG
REV	REVISION DESCRIPTION	REV DATE
<div>  <p>300 N TOWN ROAD GARRETT, IN 47603 TEL: 630 257-2100 FAX: 630 257-2100</p> </div>		
<div> <p>TITLE: FILL LINE ASSEMBLY WITH BULKHEAD FITTING &amp; ANTI-FLOOD ELBOW</p> <p>DWG NUMBER: FL-BH-AF</p> </div>		